



D.A.V. CENTENARY PUBLIC SCHOOL

KABIRMATH, KANDHWARA, SIWAN (BIHAR) 841226

Email : davcpssiwan117@gmail.com, Website : www.davcpssiwan.net.in

C.B.S.E. Affiliation No. : 330017, School No. : 65013

Managed by : DAV College Managing Committee, Chitragupta Road, New Delhi - 55

Ref. No. : DAV/CPS/SWN/2024/451


Date : 21/10/2024


TENDER NOTICE

1. Name of The Work Particulars – Wall Tiles work – 1st quality ceramic glazed wall tiles conforming to IS: 15622 (Thickness to be specified by the manufacture). 1192.74 Sqm.
 - Removing Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meters lead – 1192.74 Sqm.
 - Disposal of building rubbish / malba/ similar unserviceable, dismantled or waste materials by mechanical, means, including loading, transporting, unloading to approved municipal dumping ground or as approved by engineer – charge, beyond 50m – 90.84 Sqm.
 - 15 mm cement plaster on rough side of single or half brick wall of mix – 238.55 Sqm.
 - Chipping of whole floor area except toilets for preparing the floor surfaces rough, clean and usable for new floor tiles pasting – 834.92 Sqm.
 - 2 Time of Completion : - Three Months
 - 3 Date of Tender Notification : - 24th October-2024
 - 4 Last Date/Time for Receipt of Bids : - 30th October-2024
 - 5 Name and Address of office Inviting Tender : - Principal, DAV Centenary Public School, Kabirmath, Kandhwara Siwan, Bihar- 841226.
 - 6 Contact Number of Procurement Office : - 8797017110 (M)
 - 7 Help Numbers : - 7050641981 (M)
- Map & other work details can be had from the office of Principal, DAV Centenary Public School, Kabirmath Kandhwara, Siwan Bihar.

Following points need attention

1. There will be a security deposit of 5% of contract value.
 2. The work shall consist of all Civil Items necessary to fully complete the said work.
 3. Only the quality materials (Branded Company) and workmanship will be acceptable as per norms.
 4. Payment will be released after completion of work and verification by architect.
 5. Rates quoted should be inclusive of all taxes, no extra charges will be paid.
- Members of Building Sub-Committee.


Shanti Singh
Principal cum A.R.O.


Jyoti Sinha
Manager